



Subject: Rear Chassis Electrical Harness attachments replacement upfit interface

Model Year(s): 2020 and beyond

Models Chevrolet Silverado, GMC Sierra 3100

Affected: Series HD Cab Chassis models only

Origination Date: February 13, 2020

Revision Date: N/A

ADVISORY:

Condition/Concern:

Some Chevrolet Silverado, GMC Sierra 3600 Series Cab Chassis upfits may require alternative rear chassis harness attachments. Wiring Harness `Service Access` could be compromised when mounting an upfit body. Upfit Body mounting provisions could lock in the OEM harness/attachments.

Recommendation:

Upfit body mounting practices should allow for service of chassis wiring harness/attachments. For upfits that utilize semi-continuous `top of frame rail` contact, it is recommended that the rear electrical harness attachments be replaced with alternative `service accessible` components. The following will provide instructions for replacement of the OEM rear harness attachments if it is deemed necessary refer to figure 1.

Warning: Operate vehicle only with rear chassis electrical harness attachments and connections properly secured.




Figure 1

General Motors Upfitter Integration

<http://www.gmupfitter.com>



Instructions for Rear Harness clip replacement

(perform prior to Upfit body/equipment installation)

- 1) Remove with wiring snips, **6** of the 8 factory black plastic harness clips in areas shown (see Fig. 1) **IMPORTANT:** Do **NOT** remove the 2 factory plastic attachment clips (green area) located by the rear fuel tank lines.
- 2) Replace removed attachments with (6) new metal hoop clips & low-profile plastic push-pins as shown in Figures 2 & 3. Use recommended GM Service or OEM supplier parts listed below.
- 3) Check rear harness routing, make sure new attachments are securely fastened and harness is not chaffing chassis fuel components. Upfit body/equipment can now be installed.

Part Name	Supplier	Part Number	Required Qty.
CC Rear Harness Attachment Kit	GM Service	35447259	1 Kit
Metal Harness Hoop Clip	Aptiv	15495911	6
Fasteners	ITW ¹	39-0630-10	6

¹ Fasteners from either supplier are acceptable




Figure 2



Figure 3