

## BODY BUILDERS INSTRUCTIONS

The Incomplete Vehicle Document (IVD) is supplied with each incomplete vehicle, and provides information that should be used by intermediate and final stage manufacturers in determining conformity to applicable Federal Motor Vehicle Safety Standards (FMVSS). The IVD also includes information which must be followed in order to ensure that Environmental Protection Agency (EPA) and California emissions certification requirements and NHTSA Fuel Regulations are met.

This Body Builders Book contains information that may be used in addition to the IVD for any manufacturer making alterations to a complete/incomplete vehicle. No alteration should be made to the incomplete vehicle which either directly or indirectly results in any component, assembly or system being in nonconformance with any applicable Federal Motor Vehicle Safety Standard or Emission Regulation. Intermediate and final stage manufacturers should be familiar with all Federal Motor Vehicle Safety Standards and Emission Regulations and aware of their specific responsibilities as manufacturers.

For further assistance contact Upfitter Integration at: 1 (800) 875-4742

### Section 0 – General Instructions

Check for proper clearance between body members and chassis components which may in any way affect the reliability and performance of the vehicle by developing abrasion and wear points from moving parts or degradation from extreme environment or thermal exposure or may increase interior noise.

Check headlamp aim and all vehicle illumination systems for proper operation when the vehicle has been completed. Re-aim headlamps when necessary. Check for proper operation of windshield washer, wipers and defroster system.

Extreme care must be taken when working on vehicles equipped with Engine Control Module (ECM), Powertrain Control Module (PCM), Transmission Control Module (TCM), Vehicle Control Module (VCM) or any electronic unit associated with an inflatable restraint system. (See Owner's Manual).

If arc-welding is employed on the chassis, precautions must be taken to protect all vehicle components, especially brake and fuel lines, fuel tank assembly, electrical wiring and ECM/PCM/TCM or VCM. To avoid electronic component damage, disconnect battery (batteries); disconnect the negative cable first, followed by the positive. To reconnect cables; connect the positive first, then the negative.

When welding components to the frame assembly, remove the wax coating in the area of the weld in order to obtain secure welds. After completion of the weld, a compatible corrosion protection should be applied to the affected weld areas.

All labels on the vehicle (any message applied to the vehicle or vehicle component that informs, instructs, or warns) must appear on the completed vehicle so the user can read them easily and without obstruction.

Those installing aftermarket systems should provide information as to where and how to obtain service and replacement parts.

When installing a Power Take-Off (PTO) with hydraulic lines, the following care should be exercised:

- Route and secure all hydraulic lines so that they are not in close proximity to any parts of the exhaust system. Keep all fittings and connections away from the exhaust system. Make sure connections and fittings cannot leak on the exhaust system.
- Exhaust system heat can damage and degrade hydraulic lines and components. Oils and hydraulic fluid coming in contact with a hot exhaust system could result in a fire.

### Section 1 – Body

Accessory items such as refrigerator, hot water heater, furnace, etc., which operate on liquid propane gas should be located and protected to prevent exposure to any flame.

Body structures, interior and accessory arrangements must be designed into the vehicle to provide for proper load distribution on both axles and not to exceed any gross axle weight ratings. Lateral load equalization must also be maintained. The resultant Center of Gravity of the unladen vehicle must be within the limits tabulated in the FMVSS 105 section of the Incomplete Vehicle Document.

Body insulation provided by General Motors should not be removed. This includes any thermal or underbody heat shields. This insulation is provided to protect the vehicle body and occupants from excessive heat and/or provide noise attenuation. Any replacement material internal to the occupant compartment must be certified for FMVSS 302 Flammability of Interior Materials. Areas of specific concern, but not limited to are:

- Underbody exhaust, muffler and tailpipe shields and insulators.

- Rear load floor interior insulation.
- Front floor interior insulation.
- Dash mat insulation.
- Engine cowl insulation - interior and exterior.
- Engine cover insulation.

### **Conversions**

A minimum of 10° departure angle should be maintained if frame and/or body is extended.

If body builder installs seating other than that supplied with vehicle, it is the body builder's responsibility to ensure that the seating and restraint systems comply with FMVSS requirements. The restraint systems supplied with the vehicle were designed to accommodate the seating reference points and seat travel of the original equipment seats only.

### **Air Conditioning**

For additional information refer to **Engine - Section 6**.

**NOTE:** Air conditioning systems using R-134A refrigerant are equipped with metric fittings to prevent interchange with R-12 refrigerant components. Do not interchange R-134A components, refrigerant oil or service equipment with R-12 components, refrigerant oil or service equipment.

### **Rear Air Conditioning**

This unit may be equipped with A/C quick-connect fittings (Option YF7) on the liquid tube (high pressure) and the suction (low pressure) return tube. These fittings are designed to accept matching Aeroquip connecting fittings attached to pre-charged lines. This allows a one time only connection to the O.E.M. charged A/C system without having to discharge, evacuate and recharge for the connection of a rear A/C system.

A modification to the A/C system which causes the A/C plumbing lines to increase in length (such as the addition of a rear after-market evaporator and blower assembly) will necessitate the following changes:

- Lubrication – PAG refrigerant oil must be added to rear system to provide lubrication for compressor. Refer to Service Manual for specifications.
- Refrigerant – Add R-134A refrigerant to system based on sizing of new tubes, hoses and evaporator. Contact your A/C supplier for recommended charge.

- Label – Revise/modify GM charge label (located on top of front evaporator or A/C bottle) from factory recommended charge for a front system only to body builder's new recommended dual system per SAE J639. This is important for servicing the A/C system so that the technician knows the correct amount to add to the modified system.

## **Section 2 – Frame**

Hole drilling, welding, modifications, or alterations to the frame assembly are the responsibility of persons performing these operations. These same individuals assume complete responsibility for frame assembly reliability, performance after alterations and compliance to applicable FMVSS requirements.

The following procedures and specific precautionary instructions are recommended for proper installation of special bodies and/or equipment on GM frames. Failure to follow these recommendations could result in serious damage to the basic vehicle.

### **Flanges**

Do not drill holes in frame flanges.

### **Holes**

Holes to mount brackets, supports, and out-riggers must be drilled in the vertical side rail web with the following restrictions:

- Material between edge of hole and inside of upper or lower flange must not be less than 37 mm (1.50 in.) for HSLA (40,000 PSI yield).
- The minimum edge distance between any two (2) holes must be larger than twice the diameter of the larger hole.
- No holes should exceed 20 mm (0.75 in.) in diameter.
- All holes should be drilled in the frame using appropriate drilling practice and safety precautions.

### **Welding**

**CAUTION:** Fuel tank and fuel lines must be drained and all vapors purged to ensure non-combustible mixture before any welding, brazing or soldering.

When welding high strength low allow (HSLA 40,000 PSI yield strength) side rails or crossmembers and brackets (32,000 or 36,000 PSI yield strength), emphasis is placed upon weld application techniques to avoid stress risers that may adversely affect frame operating stresses.

When welding is performed anywhere on the vehicle, precautionary measures should be taken to prevent damage to electrical system wiring or components. Prior to any welding, parts or components which could be damaged by excessive temperatures must be removed or adequately shielded; the battery cables should be disconnected at the battery. Also prior to welding, the area to be welded and surrounding area must be cleaned of all frame protective coating. After welding, when parts are cool, carefully inspect wiring and electrical components for shorts or other damage which could draw excessive currents and possibly cause an electrical system short when the battery is reconnected. Apply protective coating to areas where coating was removed.

## **Alterations**

If the wheelbase is modified the alterer must take responsibility for compliance with affected FMVSS and for warranty on items such as driveshafts, universal joints, center bearings and rear transmission tailshaft, transfer case and transmission case fractures, output shaft bushings, bearings, brakes, fuel systems and any other related component failures. Additionally, the customer must be alerted in the modifier's owners manual that parts for the reworked area are not available through the General Motors service parts system.

## **Shear Plate Attachments**

Attachments of shear plates should be accomplished by using existing manufacturing holes already available in the frame side rails. Manufacturing holes, normally 25 mm in diameter, are consistently placed along the frame side member in the center of the web on each frame.

When additional holes are required for shear plate attachment, they should be no larger than 19 mm (0.75 in.) in diameter. Holes are to be drilled no closer than 63.5 mm (2.5 in.) apart. For holes drilled forward of the rear axle, centers are to be no closer than 63.5 mm (2.5 in.) from the top or bottom flanges and no closer than 89 mm (3.5 in.) from any suspension attachments. For frame holes drilled rearward of the rear axle, hole centers are to be no closer than 51 mm (2.0 in.) from the top or bottom flange and no closer than 89 mm (3.5 in.) from suspension attachments.

No additional holes or notching of either top or bottom frame flanges is allowed.

## **Section 3 – Front Suspension**

Since there is a large variation in completed vehicle front weight due to differences in body weight and equipment, the front suspension alignment must be checked and reset if necessary after the vehicle is completed. Caster and camber should be set with reference to the "A" dimensions.

See Truck Service Manual for complete alignment procedure, specifications and measurement of the "A" dimension under "Diagnosis and Front Alignment" section.

C/K Models are designed such that camber and caster do not need adjustment unless severe road impact or accident deformation occurs. Toe should be reset after the vehicle is completed and while at normal operating load with trim height as specified (K-Model).

## **Section 4 – Rear Suspension**

Clearance to body should be provided for the suspension, axle, driveshaft and tires under the following conditions: (1) Axle in full jounce against the metal-to-metal stop, (2) Axle at 4.5° roll with one side of axle in full jounce at the metal to metal stop and (3) Axle at design position. Allowance for the tire chain clearance shown on a maximum grown tire must allow for 42.2 mm (1.66 in.) clearance to the sides of the tire and 63.5 mm (2.5 in.) to the top of the tire. Be sure sufficient clearance is provided for suspension, axle and tire and wheel in full vertical travel (up and down).

**NOTE:** Notification to the consumer may be required in certain states if tire chains cannot be used.

Pipes, wiring, conduits and any other related components must not be placed where they cross the path of motion of the rear axle, driveshaft, axle brake pipes, hoses, spring or tires. Such crossing could result in rupture, wear-through, or separation due to normal axle motion.

See chassis data information for additional clearances and for assistance in calculating trim heights.

## **Section 5 – Brakes**

See Truck Service Manual for brake specifications.

Due to the critical nature of brake systems, anyone making modifications or alterations must assume complete responsibility for system reliability, performance and certification to FMVSS 105 or FMVSS 121.

It is mandatory that no change be made to the brake main cylinder location, brake pedal push rod length or pedal position.

Ensure that hydraulic brake system is free of air and hydraulic leaks. Bleed brakes if required, following procedures as outlined in truck chassis service manual. Ensure that vacuum booster system or hydroboost system is functional and free of leaks.

Check master cylinder fluid level and fill as necessary. (Refer to Owner's Manual)

Check power steering fluid level for models equipped with hydroboost brake. (Refer to Owner's Manual)

Added floor covering or carpeting must not restrict service or parking brake pedal travel from released position to full pedal travel.

No body part or chassis-mounted component may be located within 2.0 in. of brake hose routing in all wheel and axle positions. All exhaust system components must also have a minimum of 2.0 in. clearance to brake hoses in closest positions. (Be sure to account for brake hose travel with suspension).

Body builder is to verify that the brake warning switch is operative. The brake warning switch on models equipped with vacuum-hydraulic brakes is located on the master cylinder. This includes both the brake system fluid level and parking brake actuator switch.

## Section 6 – Engine

For additional information refer to **Body - Section 1**.

Air conditioning and auxiliary belt-driven equipment installation recommendations:

No alterations or additions to the accessory drive belt system will be warranted on serpentine belt systems.

The serpentine belt type of drive is designed as a total system, incorporating a single poly-V belt and an automatic tensioner. In this type of system, degrees of pulley wrap, belt tension, and pulley alignment are very critical factors. Modification is not recommended.

In some single belt serpentine systems, belt tension is determined by the automatic tensioner and its position relative to the belt. No adjustment required.

Due to the critical nature of the accelerator system, anyone making modifications or alterations assumes complete responsibility for system reliability, performance and compliance to FMVSS 124. Caution must be exercised so that the accelerator cable is properly routed. Specifications are as follows:

- Route cable to maximize all bend radii. In no case should bend radii be less than 3 in. (76 mm).

- Minimum distance from exhaust manifold to be 6.0 in. (150 mm), unless a heat shield is provided.
- Do not use accelerator cable or clips to route wires, harnesses or other cables. Cable sheath must be clipped so as not to pinch inner cable. Cable must not be loose in clip allowing sheath to move when accelerator pedal is applied and released.
- Cable must not be subjected to kinking or routing across any sharp edges.
- Cable routing must be perpendicular to the surface of the front-of-dash at the dash fitting. No objects or routings should force cable to have a bend at the dash fitting. Flexible components (hoses, wires, conduits, etc. ) must not be routed within 2.0 in. (50 mm) of moving parts or accelerator linkage unless routing is positively controlled.
- Caution must be taken so that the accelerator pedal remains properly located. Guidelines for accelerator pedal locations are as follows:
  - 1) Ensure that the accelerator can freely operate from idle to wide-open throttle position and return. Make sure that the pedal will not hang up on any nearby items such as carpets, floor, screws, wiring harnesses, etc. Engine cover should have at least one inch (25 mm) clearance to side of accelerator pedal with the carpet mat installed.
  - 2) Accelerator to brake pedal relationship has been designed to provide minimum driver movement and should not be altered in any way.

Gasoline engine induction and/or ignition system is certified in compliance with the Federal Vehicle Emission Standards. Any alterations to the systems or components could void compliance and render the vehicle illegal. System includes:

- Fuel system – throttle body injector (TBI) or central port injector (CPI) and associated tubes, hoses and pipes, air cleaner outside air hose and spacer heat stove and heat stove pipe, fuel pump and inlet manifold, fuel vapor canister.
- Exhaust system.
- Ignition system distributor and initial spark timing setting, spark plugs, spark plug wires.
- Crankcase ventilation system.

Diesel engine induction and injector pump system is certified to be in compliance with the Federal Vehicle Emission Standards and/or Noise Standards. Any alterations to the system or components could void compliance and render the vehicle illegal. System includes:

- Fuel system – Injection pump, injector lines and injectors, fuel return hoses and pipes, air cleaner, outside air hose, fuel pump, fuel filter, fuel heater assembly and intake manifold.

- Exhaust system.
- Crankcase pressure regulation system.
- Charge air cooler system.
- External engine components such as air cleaner, crankcase pressure regulator valve, alternator, injection pipes, fuel return hoses from injectors, exhaust manifolds, oil fill pipe, etc. must be provided with sufficient clearance for engine roll and torque.
- When a vehicle is equipped with a electronic fuel injection (EFI) engine, it has an engine control module ECM/PCM/TCM or VCM. This ECM/PCM/TCM or VCM must be maintained at a temperature below 185°F at all times. This is most essential if the vehicle is put through a paint baking process. The ECM/PCM/TCM or VCM will become inoperative if its temperature exceeds 185°F. Therefore, it is recommended that temporary insulation be placed around the ECM/PCM/TCM or VCM during the time the vehicle is in a paint oven or undergoing another high temperature process.

## Section 7 – Transmission

Light duty models equipped with manual transmission have a clutch-operated start safety switch. Starter should operate whenever the ignition is turned to start and the clutch is fully depressed. Readjust if necessary as outlined in the Truck Service Manual.

Models equipped with automatic transmissions have a steering column mounted neutral/park start safety mechanical lockout feature, which interfaces with the steering column ignition switch. Starter should operate only when gear shift lever is in neutral or park position. Readjust the shift linkage if necessary as outlined in the Truck Service Manual.

Power Take-Off (PTO) systems refer to **General - Section 0**.

- The NV4500 manual 5-speed heavy-duty overdrive transmission (RPO MW3) requires the use of special synthetic lubricant to reduce transmission internal operating temperatures. The lubricant is installed in all NV4500 transmissions at the factory.
- In instances where it is necessary to drain and refill or add fluid to the transmission, such as when installing PTO, DO NOT substitute any other lubricant. Installation of other lubricants may result in internal transmission damage.
- Castrol Syntroq GL4 is the only synthetic lubricant currently approved for use in the NV4500. This product can be secured through your local GM dealer under GM part number 12346190 per quart.
- Transmission lubricant capacity is 8.5 pints.

Models equipped with manual transmission use a hydraulic clutch actuator. Check fluid level as outlined in the vehicle owners manual.

It is mandatory that no change be made to the clutch master cylinder location, clutch master or slave cylinder push rod length, or pedal position.

## Section 8 – Fuel and Exhaust

### Fuel Systems

The fuel evaporative emission control equipment is certified to be in compliance with the Federal and California Vehicle Emission Standards. The fuel tank is molded from multi-layer plastic and should not be repaired or altered. Metal fuel lines have a surface coating to reduce corrosion on inside and outside surfaces to comply with useful life requirements. All fuel hoses, including plastic lines, are made of a low permeation multi-layer material to comply with enhanced evaporative emission requirements. Any alterations to systems or components including materials, hose lengths and their location, except as described in the fuel fill system modifications section, could void compliance. The system includes:

- Fuel tank, fuel level sender, fuel fill and vent hoses and pipes, emission canisters, fuel feed, fuel return and vapor lines, purge control solenoids, fuel fill cap, canister vent solenoid.

For these reasons,

### **NO ALTERATION OF THE FUEL SYSTEM IS RECOMMENDED**

### Fuel Fill

It is recommended that when mounting the fuel filler pipe assembly and vent hose that a minimum of 3.0 in. clearance be provided to any body component to prevent contact between hoses and/or mating parts and that retention be provided to ensure routing and prevent failure due to wear and fatigue. Both the fill and vent hoses must be routed (and supported, if needed) such that there are no sags or kinks. As viewed from the filler neck, pipes and hoses must have a downward slope toward the tank. There should be a minimum of 4° of downward slope in the fill and vent pipe at any location. No fuel traps are allowed. Alterations of fuel line routings could affect the ability of the completed vehicle and are, therefore, not desirable. The complete fuel system must comply with FMVSS 301.

If additional new hose is required when installing fuel tank filler neck, this hose must be suitable for use with unleaded fuels or diesel fuel respectively and must allow the vehicle to meet enhanced evaporative emissions requirements.

### **Fuel Lines**

Fuel line routing precautions:

- 5 in. minimum clearance to exhaust system is required or a metal shield must be provided.
- Fuel lines should be clipped to chassis to prevent chafing. Metal clips must have rubber or plastic liners.
- Use corrosion resistant steel tubing with short sections of approved hose to connect components. Hose-to-tube connections should be clamped for diesel systems. Steel tube ends should be beaded for hose retention. Fuel supply is pressurized by an in-tank pump for MPFI and SCPI systems. Coupled hose or nylon quick-connects must be used. Clamped hose is not acceptable for MPFI and SCPI systems.

All engines require a fuel return system which returns excess fuel from the injection pump and injector nozzles back to fuel tanks. Care should be taken that these lines are not blocked nor their hoses pinched. The engine may run poorly or stall if these lines are restricted or blocked.

All gasoline engine vehicles are equipped with fuel evaporative emission control equipment which is certified to be in compliance with the Federal or applicable California vehicle emission standards. Alterations to fuel tank and metering unit, lines, canister or canisters, canister filters, canister purge control valves, relay switches, tank auxiliary vent valve, engine speed controller, or other devices/systems are therefore not allowable since vehicle adherence to C.A.R.B. and Federal regulations may be affected.

Diesel powered vehicles incorporate water drain provisions in the fuel system. These valves are only to be opened when siphoning water and contaminants from the fuel system.

Body attachment brackets and u-bolts must be located such that there is adequate clearance to all fuel system components, such as the fuel lines and the fuel level sending unit, under all operating conditions.

### **Fuel Tank**

For vehicles with full frames, the tank must have a minimum clearance of 2 in. top, front, rear and sides to body and other supports.

Tank may be pressurized to 1.25 PSI maximum to check for final line leakage or for forcing fuel through the system. Pressures greater than this amount may be detrimental and affect tank durability.

**The use of auxiliary fuel tanks is not recommended.** If an auxiliary fuel tank is added, the alterer must take responsibility for compliance with affected motor vehicle safety standards. Also, if an auxiliary fuel tank is added to a gasoline-powered vehicle, the fuel must be drawn through a pipe at the top of the tank (balance line between tanks is not permitted).

Gasoline fueled vehicles are equipped with a fuel pump return line. If an auxiliary tank is added, the tank selector valve must include a return port which returns fuel to the tank from which the fuel is being drawn.

In gasoline engines the fuel pump is located in the fuel tank. The battery must be disconnected before starting any work on the fuel system.

### **Gaseous Fuel Conversions**

All truck gasoline engines may be converted to use liquified petroleum gas (LPG) or natural gas (NG); GM only approves the conversion of vehicles with option KL5 in combination with engine L31 (5.7L). However, some conversions may cause harmful effects to the engine. Such fuel systems may require assurances from alternate fuel system manufacturers and/or installers that the equipment will not cause damage to the engine or the exhaust system.

In the use of dual fuel systems, the vehicle operator should strictly adhere to the manufacturer's procedures for switching from gasoline to gaseous fuel operation. Improper switching procedures may result in overheating and damage to the exhaust system and the vehicle. The gaseous fuel tank should not be mounted in an enclosed area of the vehicle, such as the passenger compartment, truck, etc., and the system should be vented to the outside of the vehicle. In addition, vehicles converted to gaseous fuels should not be stored in enclosed places such as garages. Further, General Motors cautions purchasers that the design, location and installation of any type of fuel storage system involves significant technical and engineering considerations and that these statements on gaseous fuel conversions should not be interpreted to be an approval by General Motors of any modification to the original equipment fuel system.

Conversions to gaseous fuel should be made in conformance with applicable Federal and State regulations. Removal of emission-control components, or the addition of gaseous fuel systems which could damage or reduce the longevity of those components and could also cause the mechanical and emission performance warranty to be voided.

## **Exhaust System**

Particular care should be taken to prevent the possibility of exhaust fumes and carbon monoxide exposure to vehicle occupants in units completed by body builders. Holes and openings through the floor and all other parts of the body must be permanently and adequately sealed by the body builder to avoid exhaust intrusion into any occupant area. If it is necessary to change the exhaust outlet location, the exhaust discharge must be unobstructed and directed away from occupant areas. Alteration of the exhaust outlet or its position may increase exhaust noise and render the vehicle illegal in those areas with pass-by noise regulations. All vehicles >10,000 lbs. GVWR come under Federal noise regulations, vehicles ≤10,000 lbs. GVWR are regulated by various state and local regulations of the Environmental Protection Agency; see those regulations for rules, test procedure and noise levels permitted.

Tail pipe outlet location must be tested statically and with the vehicle in motion to ensure that exhaust gases do not penetrate side or rear windows or under body seams and holes. Auxiliary power plants should also be tested under the same conditions. Tail pipe exit ahead of rear wheels is not recommended.

Check for leaks in exhaust systems and repair as required.

Exhaust temperatures can exceed 1600°F under extreme operating conditions, with pipe surface temperatures slightly less than this. Extreme care must be used when placing body components in the proximity of the exhaust system so as not to exceed the rated temperature limits of the components. Due to variants in underbody configurations of the vehicles, we are not in a position to make recommendations on how to insulate or design components in the proximity of the exhaust system.

Each manufacturer must make temperature checks of critical areas of his vehicle and adjust his design accordingly, or provide shielding to ensure safe operation of his body components.

The same can be said for the engine compartment. Obviously there will be additional heat radiated from the engine. How much is retained in the area will depend on how well this area is ventilated in your individual designs. Here again, temperature checks of interior areas surrounding the engine should be made to determine if your insulation is adequate. This is the same engineering practice we have followed on our complete vehicles incorporating these exhaust systems.

Exhaust system materials are selected and tested to withstand the operating environment of the vehicle. **Do not modify the exhaust system in any way.** The tail pipes are made of 409 stainless steel.

Heatshields are mounted to the underbody and/or exhaust system components (catalytic converter and muffler). Shields for the propshaft hanger bearings are also provided in some vehicles.

## **Section 9 – Steering**

Check power steering fluid level and system operations. (Refer to Owner's Manual)

Steering wheel and horn pad must not be altered or replaced.

The steering column mast jacket not to be altered.

## **Section 10 – Tires**

Check wheel lug nuts for proper torque; specifications are provided in the Owner's Manual.

Substitution of tires of greater capacity than those offered as original equipment by vehicle manufacturer is not approved for use on original equipment wheels. Any usage of higher capacity tires must be accompanied by higher capacity wheels. However, the wheel offset (the distance from centerline of rim to wheel mounting face) must be the same as the replaced original equipment wheel to ensure proper wheel bearing loading and clearance of tires to body and chassis components. Increasing tire and wheel capacity does not necessarily increase vehicle GVW ratings.

Any substitution of tires may affect Speedometer/Odometer accuracy.

It is recommended that tire chain clearance guideline, J683 from the Society of Automotive Engineers be adhered to in designing rear wheelhouse clearance.

Check tires and inflate to recommended tire pressure according to the tire pressure information provided in Owner's Manual and tire inflation label provided with vehicle.

## **Section 12 – Electrical Battery and Battery Cables**

The vehicle battery should be located and positioned to make use of the existing battery cables. If the battery requires relocation and longer cables are required, a proportionately larger gauge wire must be used. If in relocating the battery the negative ground cable is attached to frame rail, a cable of similar gauge be provided between the frame rail and the engine. This is required due to the heavy electrical loads imposed by the starting circuit. To ensure proper operation of the battery cables the following chart on length, gauge and materials must be strictly adhered to:

Combined length of positive and negative	
Cable Gauge	Cable in Inches (Copper)
4	66
2	107
0	170

If the battery is remotely mounted (other than in the engine compartment) the 'sense' circuit in the generator regulator shall be used. The sense circuit consists of a 7.76 OHM 1/4 watt resistor connected in series between the 'S' terminal of the generator and the B+ terminal of the battery.

#### **Auxiliary Battery (Gasoline Engines Only)**

If an auxiliary battery is to be retro-fitted, the electrical schematic for option TP2 is recommended as a guide. This will result in the auxiliary battery being connected to the vehicle load and charging circuit when the ignition switch is 'on' (fuse block terminal "Acc.Ign.Fused"). When the ignition switch is turned off, the interlocking relay is disengaged and the auxiliary battery is disconnected from the vehicle circuit.

Modifications/add-on wiring must be carefully reviewed to ensure compatibility with the base vehicle wiring by reviewing system schematics, wire routing paths, harness connections, etc. Due to the wide range of modifications that may be required for vocational needs, it is not feasible for the O.E.M. to take into account all potential revisions. For this reason, any person modifying existing vehicle wiring must assume responsibility that the revisions have not degraded the electrical system performance. Any add-on wiring must be properly fused and routed to prevent cut, pinch, and chafe problems, as well as avoid exposure to excessive heat. Care must be exercised that existing vehicle interfaces do not have their current load capabilities exceeded, and that the respective control devices are not overloaded. Added wire size should be at least as large as the wire to which it is attaching in order for fuse protection to be maintained.

A Packard electric wiring repair kit is available through Kent-Moore (GMP/N 12085264, Kent-Moore P/N J38125-4). This kit contains instructions, tools and components for making repairs to wiring harness components. This kit would also greatly assist in accomplishing necessary add-on wiring such as body marker lamps, so that system reliability/durability is maintained.

Electrical wiring components can be obtained through your authorized GM dealer. Many Packard Electric components are also available through Pioneer Standard Company (1-800-PACKARD). Pioneer may also be able to assist in making necessary wiring additions by providing custom wiring stubs or jumpers to your specifications.

### **Section 13 – Cooling**

To provide satisfactory engine cooling, the following conditions must be met:

1. Do not locate any large objects in front of the radiator core or grille such as batteries, spare tires, lights/sirens, etc. They restrict air flow into the radiator core and influence fan blade stress.
2. Grille opening, size configuration and the external baffles provided should not be altered in any manner. Any reduction in cooling ability may adversely affect engine/transmission performance.
3. Fan clutches not conforming to the original equipment specifications may not operate correctly and may stay "on" continuously, never come on, or cycle on and off excessively. This will result in a reduction of fuel economy, engine overheat at times, and annoying cycling respectively.
4. Heavy duty cooling equipment is required when snow plows, winches, etc. are installed.
5. If a heater unit is not installed in the vehicle or a heater shut-off valve is required, a line connecting the heater connection on the engine to the heater connection on the engine must be installed. When a shut-off valve is required in heating system, it must be teed into the system in such a manner as to maintain continuous flow between engine heater connection - radiator heater connection at all times.

Do not install any internal flow restrictors.

- Heater hose:  
3-way or 4-way valves must be used to provide constant water flow through the intake manifold pad area used to mount the TBI unit (L35 only).


**NOTE:** TBI unit does not have internal coolant passages.



## Model Symbol Chart

Series	2 Door Pickup Fleetside/ Wideside	2 Door Pickup Sportside	3 Door Extended Cab Rear Seat Acces Panel Fleetside/ Wideside	3 Door Extended Cab Rear Seat Access Panel Sportside	GVW (lbs.)	Nominal Ton Rating	Wheelbase (in.)	Cab to Axle (in.)
C/K 157	03 + E63 (6.5' Box)	03 + E62 (6.5' Box)			C/K 6100	1/2	119.0	42
			53 + E63 (6.5' Box)	53 + E62 (6.5' Box)	C 6200 K 6400	1/2	143.5	42
C/K 159	03 + E63 (8.0' Box)				C/K 6400	1/2	133.0	56
			53 + E63 (8.0' Box)		C 6200 K 6400	1/2	157.5	56
C/K 257			53 + E63 (6.5' Box)		C/K 7200 K 8600	3/4	143.5	42
C/K 259	03 + E63 (8.0' Box)				C 7200 C/K 8600	3/4	133.0	56
			53 + E63 (8.0' Box)		C 7200 & L56 C/K 8600	3/4	157.5	56

## C/K (15/25)703 General Arrangement




## ***SNOWPLOW INSTALLATION***

Information not available at time of publication due to incomplete barrier testing and validation.


## ***PICKUP BOX REMOVAL PROGRAM***

Information not available at time of publication due to incomplete barrier testing and validation.


## C/K 15703 Regular Cab with Short box



## C/K (15/25)903 Regular Cab with Long Box




C/K 15703 Regular Cab, Sportside






## C/K (15/25)953 Extended Cab with Long Box







## C/K 15753 Extended Cab, Sportside




## C/K (15/25)(7/9)03 Regular Cab Interior




## C/K (15/25)(7/9)53 Extended Cab Interior




C/K (15/25)(7/9)(03/53) Interior Seating Positions




## C/K (15/25)(7/9)(03/53) Front Floor Seat Mounting Locations



## C/K (15/25)(7/9)03 Regular Cab Exterior




## C/K (15/25)(7/9)53 Extended Cab Exterior




## C/K (15/25)(7/9)(03/53) Door Openings

NOTE:  
FRONT DOORS ARE  
COMMON FOR ALL  
T800 MODELS




ALL DIMENSIONS SHOWN  
FOR CHEVY BASE MODEL  
UNLESS OTHERWISE NOTED




NOTE:  
REAR DOORS FOR  
EXTENDED CABS ONLY




## C/K (15/25)(7/9)(03/53) Front End Sheet Metal




## C/K (15/25)(7/9)(03/53) Outside, Rearview Mirror Options




\*DF2 AVAILABLE  
NOTE: MIRROR SHIPPED LOOSE



\*OPTION D44 BASE FOR CLASS-2-  
(EXPORT ONLY)




\*BASE D48 (REMOTE ELECTRICAL)



\*BASE DE2 (MANUAL)

## C/K (15/25)(7/9)(03/53) Cab Profile Nominal, Regular/Extended Cab




DRIVER SIDE COORDINATES

PT #	WIDTH	HEIGHT
1	-958.74	1200.00
2	-938.08	1264.98
3	-911.62	1300.00
4	-900.00	1350.59
5	-888.05	1400.00
6	-873.75	1452.70
7	-859.42	1500.00
8	-845.94	1540.87
9	-824.57	1600.00
10	-800.00	1661.35
11	-783.23	1700.00

PT #	WIDTH	HEIGHT
12	-751.80	1766.91
13	-734.80	1800.00
14	-724.51	1818.00
15	-714.22	1831.97
16	-700.00	1844.60
17	-677.79	1855.90
18	-655.00	1863.47
19	-625.19	1867.85
20	-600.00	1870.63
21	-550.40	1874.64
22	-500.00	1878.10

PT #	WIDTH	HEIGHT
23	-440.45	1881.76
24	-400.00	1884.02
25	-352.43	1886.44
26	-300.00	1888.82
27	-247.74	1890.81
28	-200.00	1892.29
29	-143.45	1893.59
30	-100.00	1894.30
31	-65.20	1894.69
32	-26.00	1894.94
33	000.00	1895.00


C/K (15/25)(7/9)(03/53) Hood Profile (Chevy)



PT #	LENGTH	WEIDTH
1	1300.0	-877.8
2	1249.8	-878.8
3	1200.0	-876.2
4	1150.9	-873.2
5	1100.0	-820.1
6	1035.0	-866.4
7	1000.0	-864.2
8	933.5	-860.2
9	900.0	-858.1
10	853.6	-855.3
11	800.0	-851.9
12	736.2	-847.8
13	700.0	-845.4
14	637.8	-841.0
15	600.0	-838.1
16	539.9	-838.1
17	500.0	-829.6
18	442.9	-824.0
19	400.0	-819.4
20	339.2	-812.7
21	326.4	-800.0
22	308.6	-757.2
23	300.0	-734.2
24	287.9	-700.0
25	270.0	-644.6
26	257.0	-600.0
27	242.0	-543.7
28	231.4	-500.0
29	216.9	-433.0
30	210.5	-400.0
31	200.0	-341.1
32	193.5	-300.0
33	184.7	-237.2
34	180.2	-200.0
35	175.8	158.3
36	170.6	-100.0
37	166.6	-39.6
38	164.6	00.0

DRIVER SIDE COORDINATES


## C/K (15/25)(7/9)(03/53) Hood Profile (GMC)



PT#	LENGTH	WIDTH
1	1000.0	-863.8
2	900.0	-857.7
3	800.0	-851.5
4	700.0	-845.0
5	600.0	-837.7
6	500.0	-829.2
7	400.0	-819.0
8	364.4	-815.2
9	343.4	-812.4
10	334.5	-800.0
11	317.2	-772.3
12	300.0	-739.7
13	281.9	-700.0
14	267.8	-663.5
15	254.9	-629.0
16	244.5	-600.0
17	232.7	-568.8
18	223.3	-536.5
19	215.5	-500.0
20	209.0	-464.0
21	200.0	-410.0
22	197.9	-400.0
23	192.0	-358.1
24	183.7	-300.0
25	178.3	-249.7
26	173.5	-200.0
27	168.6	-141.8
28	165.6	-100.0
29	163.6	-33.5
30	161.5	00.0


DRIVER SIDE COORDINATES

## C/K (15/25)(7/9)(03/53) Hood Inner Panel




## C/K (15/25)(7/9)(03/53) Stake Pockets


8.0 FLEETSIDE PICKUP BOX




6.5 FLEETSIDE PICKUP BOX




6.5 SPORTSIDE PICKUP BOX




## C/K (15/25)(7/9)(03/53) Fleetside




VIEW IN CIRCLE (A)



SECTION A-A




	A	B	C	D	E	F	G	H	J
C/K 6.5FT	2093.6 (82.4)	2037.6 (80.2)	508.3 (20.0)	369.6 (14.6)	1079.1 (42.5)	2595.3 (102.2)	2120.0 (83.5)	1975.1 (77.8)	2055.7 (80.9)
C/K 8.0FT	2574.2 (101.3)	2517.6 (99.6)	632.7 (24.9)	724.6 (28.5)	1437.5 (56.6)	3075.0 (121.1)	2600.0 (102.4)	2455.1 (96.7)	2544.2 (100.2)






## C/K (15/25)(7/9)(03/53) Fleetside, Top Rail




## C/K (15/25)(7/9)(03/53) Fleetside, Inner Side Panel


VIEW IN CIRCLE A




SECTION B-B




VIEW IN CIRCLE D




SECTION C-C  
TIE DOWN LOOP



VIEW IN CIRCLE E



NOTE: ALL POCKET SIZE DIMENSIONS ARE APPROXIMATE




ALL LENGTH DIMENSIONS FROM INSIDE FLANGE




ALL LENGTH DIMENSIONS FROM INSIDE FLANGE

NOTE: R.H. SYMETRICAL ABOUT  $\bar{C}$

## C/K 157(03/53) Sportside




C/K 157(03/53) Sportside, Top Rail




## C/K 157(03/53) Sportside, Inner Side Panel


SECTION A-A  
(TIE DOWN LOOP)




SECTION B-B




VIEW IN CIRCLE C



NOTE: ALL POCKET SIZE DIMENSIONS ARE APPROXIMATE




VIEW IN CIRCLE D




NOTE: R.H. SYMETRICAL ABOUT C


## C/K 15703 Rail and Crossmember Arrangement



## C/K 15903 Rail and Crossmember Arrangement



## C/K 25903 Rail and Crossmember Arrangement




PICKUP BOX MOUNTING HOLE LOCATIONS MARKED THUS Δ 8 PLACES. DIMENSIONS OF MOUNTING HOLES ARE SYMMETRICALLY OPPOSITE ABOUT CENTERLINE OF VEHICLE.

[ ] = INCHES


"C" SERIES SAME AS EXCEPT AS NOTED

FOR DETAIL INFO ON FRT FRAME SEE "C" TD005323 "K" TD005326





## C/K 15753 Rail and Crossmember Arrangement




PICKUP BOX MOUNTING HOLE LOCATIONS MARKED THUS  $\Delta$  8 PLACES. DIMENSIONS OF MOUNTING HOLES ARE SYMMETRICALLY OPPOSITE ABOUT CENTERLINE OF VEHICLE.

[ ] = INCHES


"C" SERIES SAME AS EXCEPT AS NOTED

FOR DETAIL INFO ON FRT FRAME SEE "C" TD005324 "K" TD005325

C/K 15953 Rail and Crossmember Arrangement




## C/K 25753 Rail and Crossmember Arrangement







## C 15000 Front Frame




C 2500 Front Frame



## K 1500 Front Frame




K 2500 Front Frame







## C/K (15/25)000 Spare Tire Carrier




MODEL	TIRE	A	B
C/K25753	LT225/75R16	895.2 [ 35.24 ]	58.6 [ 2.31 ]
C/K15703	P235/75R16	877.7 [ 34.56 ]	80.5 [ 3.17 ]
C/K25903	LT245/75R16	906.1 [ 35.67 ]	67.1 [ 2.64 ]
C/K15953	P245/75R16	881.9 [ 34.72 ]	77.8 [ 3.06 ]


MODEL	D
703-753	209.3
903-953	204.1
TO HOLE IN BUMPER	209.08




C/K (15/25)000 Platform Hitch Mounting



[ ] = INCHES  
 CK HITCH MOUNT



## C (15/25)000 Front Axle/Tire Data, 2 Wheel Drive




\*MINIMUM GROUND CLEARANCE TO BE CALCULATED BY USING GROSS AXLE WEIGHT AND RECOMMENDED TIRE PRESSURE

() = INCHES  
TD005335

MODEL	TIRE	MAX GVW	REAR WHEEL	TRACK	WHEEL OFFSET	GROUND CLEARANCE	MAX TIRE WIDTH
C15703	P235/75R16	6100	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	252.0 (9.9)
	P255/70R16	6100	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	268.0 (10.6)
C15753	P235/75R16	6200	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	252.0 (9.9)
	P255/70R16	6200	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	268.0 (10.6)
C15903	P235/75R16	6400	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	252.0 (9.9)
	P255/70R16	6400	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	268.0 (10.6)
C15953	P235/75R16	6200	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	252.0 (9.9)
	P255/70R16	6200	SINGLE	1651.0 (65.0)	31.0 (1.2)	202.8 (8.0)	268.0 (10.6)
C25753	LT225/75R16D	7200	SINGLE	1666.0 (65.6)	28.0 (1.1)	190.4 (7.5)	239.0 (9.4)
	LT245/75R16E	7200	SINGLE	1666.0 (65.6)	28.0 (1.1)	202.4 (8.0)	256.0 (10.1)
C25903	LT225/75R16D	7200	SINGLE	1666.0 (65.6)	28.0 (1.1)	190.4 (7.5)	239.0 (9.4)
	LT245/75R16E	7200/8600	SINGLE	1666.0 (65.6)	28.0 (1.1)	202.4 (8.0)	256.0 (10.1)
C25953	LT225/75R16D	7200	SINGLE	1666.0 (65.6)	28.0 (1.1)	190.4 (7.5)	239.0 (9.4)
	LT245/75R16E	7200/8600	SINGLE	1666.0 (65.6)	28.0 (1.1)	202.4 (8.0)	256.0 (10.1)

K (15/25)000 Front Axle/Tire Data, 4 Wheel Drive



TDO05336


K15/25 FRONT AXLE/TIRE DATA CHART

\*MINIMUM GROUND CLEARANCE TO BE CALCULATED BY USING GROSS AXLE WEIGHT & RECOMMENDED TIRE PRESSURE

[ ]= INCHES

MODEL	TIRE	MAX GVW	REAR WHEEL	TRACK	WHEEL OFFSET	GROUND CLEARANCE	MAX TIRE WIDTH
K15703	P245/75R16	6100	SINGLE	1651.0 165.01	31.0 [1.2]	214.7 [8.5]	261.0 [10.3]
	P265/75R16	6100	SINGLE	1651.0 165.01	31.0 [1.2]	227.7 [9.0]	276.0 [10.9]
	LT245/75R16C	6100	SINGLE	1651.0 165.01	31.0 [1.2]	229.7 [9.0]	256.0 [10.1]
K15753	P245/75R16	6400	SINGLE	1651.0 165.01	31.0 [1.2]	214.7 [8.5]	261.0 [10.3]
	P265/75R16	6400	SINGLE	1651.0 165.01	31.0 [1.2]	227.7 [9.0]	276.0 [10.9]
	LT245/75R16C	6400	SINGLE	1651.0 165.01	31.0 [1.2]	229.7 [9.0]	256.0 [10.1]
K15903	P245/75R16	6400	SINGLE	1651.0 165.01	31.0 [1.2]	214.7 [8.5]	261.0 [10.3]
	P265/75R16	6400	SINGLE	1651.0 165.01	31.0 [1.2]	227.7 [9.0]	276.0 [10.9]
	LT245/75R16C	6400	SINGLE	1651.0 165.01	31.0 [1.2]	229.7 [9.0]	256.0 [10.1]
K15953	P245/75R16	6400	SINGLE	1651.0 165.01	31.0 [1.2]	214.7 [8.5]	261.0 [10.3]
	P265/75R16	6400	SINGLE	1651.0 165.01	31.0 [1.2]	227.7 [9.0]	276.0 [10.9]
	LT245/75R16C	6400	SINGLE	1651.0 165.01	31.0 [1.2]	229.7 [9.0]	256.0 [10.1]
K25753	LT245/75R16C	7200	SINGLE	1742.0 168.61	28.0 [1.1]	198.2 [7.8]	239.0 [9.4]
	LT245/75R16C	7200/8600	SINGLE	1742.0 168.61	28.0 [1.1]	210.2 [8.3]	256.0 [10.1]
K25903	LT245/75R16C	8600	SINGLE	1742.0 168.61	28.0 [1.1]	210.2 [8.3]	256.0 [10.1]
K25953	LT245/75R16C	8600	SINGLE	1742.0 168.61	28.0 [1.1]	210.2 [8.3]	256.0 [10.1]

## C/K (15/25)000 Rear Axle/Tire Data





TIRE CHAINS NOT INCLUDED  
 SINGLE WHEELS  
 A = TRACK + F  
 B = TRACK - F

SERIES	TIRES	GVW RANGE	REAR WHEEL	TRACK	WHEEL OFFSET	DIM A	DIM B	DIM C	DIM D	DIM E *	DIM F **
C1500	P235/75R16	6100/6400	SINGLE	1676.4 [66.0]	31.0 [1.2]	1928.4 [75.9]	1424.4 [56.1]	149.8 [5.9]	236.3 [9.3]	385.0 [15.2]	252.0 [9.9]
	P255/70R16	6100/6400	SINGLE	1676.4 [66.0]	31.0 [1.2]	1944.4 [76.6]	1408.4 [55.5]	141.7 [5.6]	239.4 [9.4]	388.0 [15.3]	268.0 [10.6]
K1500	LT245/75R16	6100/6400	SINGLE	1676.4 [66.0]	31.0 [1.2]	1937.4 [76.3]	1415.4 [55.7]	144.7 [5.7]	205.2 [8.1]	396.0 [15.6]	261.0 [10.3]
	P245/75R16	6100/6400	SINGLE	1676.4 [66.0]	31.0 [1.2]	1937.4 [76.3]	1415.4 [55.7]	147.3 [5.8]	204.1 [8.0]	395.0 [15.6]	261.0 [10.3]
	P265/75R16	6100/6400	SINGLE	1676.4 [66.0]	31.0 [1.2]	1952.4 [76.9]	1400.4 [55.1]	136.4 [5.4]	219.2 [8.6]	410.0 [16.1]	276.0 [10.9]
C2500	LT225/75R16	7200	SINGLE	1676.4 [66.0]	28.0 [1.1]	1915.4 [75.4]	1437.4 [56.6]	155.9 [6.1]	190.1 [7.5]	381.0 [15.0]	239.0 [9.4]
	LT245/75R16	7200	SINGLE	1676.4 [66.0]	28.0 [1.1]	1932.4 [76.1]	1420.4 [55.9]	146.6 [5.8]	202.9 [8.0]	396.0 [15.6]	256.0 [10.1]
	LT245/75R16	8600	SINGLE	1676.4 [66.0]	28.0 [1.1]	1932.4 [76.1]	1420.4 [55.9]	146.6 [5.8]	202.9 [8.0]	396.0 [15.6]	256.0 [10.1]
K2500	LT225/75R16	7200	SINGLE	1676.4 [66.0]	28.0 [1.1]	1915.4 [75.4]	1437.4 [56.6]	155.9 [6.1]	190.1 [7.5]	381.0 [15.0]	239.0 [9.4]
	LT245/75R16	7200	SINGLE	1676.4 [66.0]	28.0 [1.1]	1932.4 [76.1]	1420.4 [55.9]	146.6 [5.8]	202.9 [8.0]	396.0 [15.6]	256.0 [10.1]
	LT245/75R16	8600	SINGLE	1676.4 [66.0]	28.0 [1.1]	1932.4 [76.1]	1420.4 [55.9]	146.6 [5.8]	202.9 [8.0]	396.0 [15.6]	256.0 [10.1]


C15 & 25 REAR TIRE DATA CHART  
 TD005337

26 Gallon Fuel Tank




FUEL TANK 26 GAL  
DRAW CAPACITY  
[ ] = INCHES

## 34 Gallon Fuel Tank



## 4.3L Gas Engine, Option L35




[ ] = INCHES

UNLESS OTHERWISE SPECIFIED  
ALL DIMENSIONS ARE TO  
NORMAL TOP OF FRAME


EXHAUST, OPTION L35  
4.3L GAS ENGINE



## 4.8L Gas Engine, Option LR4



## 5.3L Gas Engine, Option LM7




[ ] = INCHES

UNLESS OTHERWISE SPECIFIED  
ALL DIMENSIONS ARE TO  
NORMAL TOP OF FRAME

EXHAUST OPTION LM7/LR4



6.5L Turbo Diesel, Option L65



UNLESS OTHERWISE SPECIFIED  
ALL DIMENSIONS ARE TO  
NORMAL TOP OF FRAME

[ ] = INCHES

C/K25753 FRAME

EXHAUST, OPTION L65  
6.5L TURBO DIESEL